

Swiss Agency for Development

Grid Integration Report

[Chepuri Kandor, Bochapukur, Kajol Porchim, Kala Kandor] Bangladesh Wakil Ahmed Arnob, Shisher Shrestha, Md. Abdullah Al Matin, Archisman Mitra

About IWMI: The International Water Management Institute (IWMI) is an international, research-for development organization that works with governments, civil society, and the private sector to solve water problems in developing countries and scale up solutions. Through the partnership, IWMI combines research on the sustainable use of water and land resources, knowledge services, and products with capacity strengthening, dialogue, and policy analysis to support the implementation of water management solutions for agriculture, ecosystems, climate change, and inclusive economic growth. Headquartered in Colombo, Sri Lanka, IWMI is a CGIAR Research Center with offices in 14 countries and a global network of scientists operating in more than 30 countries.

About CGIAR: CGIAR is a global research partnership for a food-secure future. CGIAR science is dedicated to transforming food, land, and water systems in a climate crisis. Its research is carried out by 13 CGIAR Centres/Alliances in close collaboration with hundreds of partners, including national and regional research institutes, civil society organizations, academia, development organizations and the private sector. www.cgiar.org

About SoLAR: Solar Irrigation for Agricultural Resilience (SoLAR) in South Asia aims to sustainably manage the water-energy and climate interlinkages in South Asia through the promotion of solar irrigation pumps (SIPs). The project's main goal is to contribute to climate-resilient, gender-equitable, and socially inclusive agrarian livelihoods in Bangladesh, India, Nepal, and Pakistan by supporting government efforts to promote solar irrigation. This project responds to government commitments to transition to clean energy pathways in agriculture. All countries in this project have NDC commitments to reduce greenhouse gas (GHG) emissions, and SIPs can play a significant role in reducing emissions in agriculture.

About SDC: The Swiss Agency for Development and Cooperation (SDC) is the agency for international cooperation of the Federal Department of Foreign Affairs (FDFA). Swiss International Cooperation, an integral part of the Federal Council's foreign policy, aims to contribute to a world without poverty and in peace for sustainable development. SDC, through its Global Program Climate Change and Environment (GPCCE), helps find solutions to global challenges linked to climate change. It engages in global political dialogue and manages specific projects in the fields of energy, climate change adaptation, sustainable development of mountainous regions, and prevention of natural hazards that are likely to influence regional and international policy.

About IDCOL: Infrastructure Development Company Limited (IDCOL) was established on 14 May 1997 by the Government of Bangladesh. The Company was licensed by the Bangladesh Bank as a non-bank financial institution (NBFI) on 5 January 1998. Since its inception, IDCOL is playing a major role in bridging the financing gap for developing medium to large-scale infrastructure and renewable energy projects in Bangladesh. The company now stands as the market leader in private sector energy and infrastructure financing in Bangladesh.

Authors: Wakil Ahmed Arnob, Shisher Shrestha, Md. Abdullah Al Matin, Archisman Mitra

Wakil Ahmed Arnob: Management Trainee, Renewable Energy Projects, IDCOL

Shisher Shrestha: National Researcher - Renewable Energy Water and Climate Change Climate Change Adaptation, IWMI

Md. Abdullah Al Matin: Assistant Vice President (Technical), Renewable Energy Projects, IDCOL

Archisman Mitra: Regional Researcher· Economics and Impact Assessment, IWMI

Disclaimer: This publication has been prepared with care. Responsibility for editing, proofreading, and layout, opinions expressed, and any possible errors lies with the authors and not the institutions involved. The boundaries and names shown, and the designations used on maps do not imply official endorsement or acceptance by IWMI, CGIAR, our partner institutions, or donors.

Copyright © 2023, by IWMI. All rights reserved. IWMI encourages the use of its material provided that the organization is acknowledged and kept informed in all such instances.

Please send inquiries and comments to iwmi-solar@cgiar.org

A free copy of this publication can be downloaded at https://solar.iwmi.org/reports/

Acknowledgments

This report is a part of the Solar Irrigation for Agricultural Resilience (SoLAR) project supported by the Swiss Agency for Development and Cooperation (SDC). The Infrastructure Development Company Limited (IDCOL) is the main project partner for the SoLAR-SA project in Bangladesh. We express our gratitude to the Gazi Group for sharing data and providing valuable insights. We also thank Mr. Tanmoy Bhaduri, IWMI and Ms. Shibani Chattopadhyay, IWMI for their editorial support and Mr. Aariz Raza, IWMI for his support in designing the report.

Donor



Swiss Agency for Development and Cooperation (SDC)

Partner



Gazi Group

Contents

| 1. Introduction | 8 |
|---|----|
| 2. Background on Grid Integration Pilot | 9 |
| 2.1 Grid Integration of Solar Irrigation Pump [Model] | 9 |
| 2.2 Site selection | 10 |
| 2.3 Site details | 10 |
| 3. Detailed Commissioning Report | 12 |
| 3.1 System Summary of Grid Connection Infrastructure | 14 |
| 3.2 Array details | 15 |
| 3.3 On-grid Inverter details | 20 |
| 4. Implementation of the Grid Connection Pilot | 21 |
| 4.1 Technical details | 22 |
| 4.2 Financial details | 22 |
| 5. Monitoring and O&M | 23 |
| 6. Conclusion. | 23 |

1. Introduction

Solar-based irrigation systems are an innovative and an environment-friendly solution for the diesel-dependent agro-economy of Bangladesh. The deployment of Solar Irrigation Pumps (SIP) in agriculture has the potential to simultaneously address two of the Sustainable Development Goals (SDGs) – one of which is SDG-2 (zero hunger), and another is SDG-7 (affordable and clean energy). SIPs are seen as one of the most promising uses of renewable energy that simultaneously provide access to energy and contribute to food production. Presently, the country has 1.34 million diesel pumps and 0.27 million electric pumps for irrigation purposes¹. The diesel-run pumps consume at least 1 million tons of diesel worth \$900 million per year, and the electricity-run pumps consume about 150 megawatt of power [BPDB-2015-2016]. It is important to note that Bangladesh has good solar resources, with high availability during the peak irrigation season; therefore, solar pumping of water for irrigation is a potential solution for its largely agro-based economy. The Infrastructure Development Company Limited (IDCOL), a government-owned financial institution, is implementing the Off-grid Solar Irrigation Pumps (SIPs) Program for their Partner Organizations (POs) to off-grid areas to reduce dependency on diesel and to benefit the farmers and marginalized populations.

However, the demand for irrigation in Bangladesh is seasonal, and the primary use of solar irrigation pumps is between 4-5 months during the year, mostly for the Boro crop that is grown between Jan-May. For the rest of the year, SIPs remain mostly unutilized. Since these SIPs tend to remain underutilized over a significant portion of the year, which could be as high as 210 days in a year, most of the electricity generated from solar panels is getting wasted. If arrangements are made to supply electricity from these systems into the national grid during the off-season, paths to exploit the untapped potential will open up. Simultaneously, the Government envisions providing access to clean, affordable, and grid-quality electricity to all its citizens, as manifested by its efforts to expand the national grid. Thus, it is very likely that both the technical and financial challenges of integrating a huge number of off-grid SIP systems to the national grid will need to be tackled in the near future. The Sustainable and Renewable Energy Development Authority (SREDA) of Bangladesh has already piloted a successful Solar Grid Integration System in Kushtia district and has prepared a draft guideline for grid integration of SIPs. The guideline envisages the power distribution company to buy excess electricity from solar irrigation systems². As a result, solar irrigation systems are going to become more popular, and additional revenue from grid integration of SIPs will make SIPs financially sustainable and work to support smaller farmers and marginalized communities, including women and youth.

¹https://www.worldbank.org/en/results/2015/09/08/solar-powered-pumps-reduce-irrigation-costs-bangladesh

²https://www.bangladeshpost.net/posts/first-grid-integration-of-solar-irrigation-pump-successful-17684

2. Background on Grid Integration Pilot

2.1 Grid Integration of Solar Irrigation Pump [Model]

Under IDCOL, GREL is implementing four individual Solar Irrigation Grid Integration systems in a cluster model. Technical solutions are there for integrating solar-powered irrigation pumps into the national grid during the off-season where the SIP already exists. For grid integration of individual SIPs, a DC circuit breaker, an interlocking switch, an inverter, and a unidirectional meter are required. During off irrigation season, when the SIP is not operational, the PV array will only export electricity to the grid via the inverter. The component specifications of the SIP systems shall comply with the standards to be set by Sustainable and Renewable Energy Development Authority (SREDA) and the local body *Palli Bidyut Somitis* (PBS) under the Bangladesh Rural Electrification Board (BREB). It will be the net amount of exported electricity at the end of settlement period as per this guideline.




Figure 3.3: Schematic diagram of cluster type grid integration of SIP (Three Phase) Source: SIP Draft Guideline by Sustainable Renewable Energy Development Authority (SREDA)

2.2 Site selection

The **process and the rationale** for the selection of **pilot locations**, and as per the SREDA SIP Grid Integration Policy, is that excess power can only be exported from the SIP to the grid, so sites have been selected where the pumps are near the grid line and comparatively have less irrigation coverage.

2.3 Site details




Figure: Location of four SIP sites

GAZI has installed 431 no. of SIPs in four phases. Out of these 4 sites namely Chepuri Kandor (Site 1), Bocha Pukur (Site 2), Kajol Porchim (Site 3), and Bala Kandor (Site 4) has been grid integrated in a cluster mode. Sites 1, 2 and 3 are the pumps of phase 2 and site 4 is the pump of phase 3. Specific details for each site are provided below.

Site 1: Chepuri Kandor Solar Irrgiation Pump, Boro Bochapukur, Nijpara, Birganj, Dinajpur

| SITE NAME | Chepuri Kandor Solar Irrigation Pump |
|----------------------------|--|
| SIP ID | 5220GZI0200123 |
| LOCATION | BoroBochapukur, Nijpara, Birganj, Dinajpur |
| PROJECT COST | 66,231 USD |
| SUPPORTED BY | THE WORLD BANK, jica |
| FINANCED BY | IDCOL |
| EPC CONTRACTOR | Solargao Ltd |
| COMMISSIONING DATE | 03.05.2017 |
| TECHNICAL DETAILS | |
| FLOW RATE | 1802000 L/day |
| BORING DEPTH | 160 |
| Solar PV SIZE (kWp) | 30 |
| Individual Panel Size (Wp) | 250 |
| Number of Panels | 120 |
| Pump Size (kW) | 15kw |
| Controller Size (kW) | 15kw |
| GPS COORDINATES | 25.8860508, 88.6456058 |

Site 2: Bocha Pukur Solar Irrgiation Pump, Pubo Chakay, Nijpara, Birganj, Dinajpur

| SITE NAME | Bocha Pukur Solar Irrigation Pump |
|----------------------------|--|
| SIP ID | 5220GZI020021 |
| LOCATION | PuboChakay, Nijpara, Birganj, Dinajpur |
| PROJECT COST | 66,231 USD |
| SUPPORTED BY | THE WORLD BANK, jica |
| FINANCED BY | IDCOL |
| EPC CONTRACTOR | Solargao Ltd |
| COMMISSIONING DATE | 03.05.2017 |
| TECHNICAL DETAILS | |
| FLOW RATE | 18,02,000 L/day |
| BORING DEPTH | 160 |
| Solar PV SIZE (kWp) | 30 |
| Individual Panel Size (Wp) | 250w |
| Number of Panels | 120 |
| Pump Size (kW) | 15kw |
| Controller Size (kW) | 15kw |
| GPS COORDINATES | 25.8829825,88.6468423 |
| | |

Site 3: Kajol Porchim Solar Irrgiation Pump, Boro Bochapukur, Nijpara, Birganj, Dinajpur

| SITE NAME | Kajol Porchim Solar Irrigation Pump |
|----------------------------|--|
| SIP ID | 5220GZI020067 |
| LOCATION | BoroBochapukur, Nijpara, Birganj, Dinajpur |
| PROJECT COST | 66,231 USD |
| SUPPORTED BY | THE WORLD BANK, jica |
| FINANCED BY | IDCOL |
| EPC CONTRACTOR | Solargao Ltd |
| COMMISSIONING DATE | 03.05.2017 |
| TECHNICAL DETAILS | |
| FLOW RATE | 18,02,000 L/day |
| BORING DEPTH | 160 |
| Solar PV SIZE (kWp) | 30 kWp |
| Individual Panel Size (Wp) | 250w |
| Number of Panels | 120 |
| Pump Size (kW) | 15kw |
| Controller Size (kW) | 15kw |
| GPS COORDINATES | 25.8845525,88.6424180 |

Site 4: Bala Kandor Solar Irrgiation Pump, Boro Bochapukur, Nijpara, Birganj, Dinajpur

| SITE NAME | Bala Kandor Solar Irrigation Pump |
|--------------------|--|
| SIP ID | 5220GZI0327 |
| LOCATION | BoroBochapukur, Nijpara, Birganj, Dinajpur |
| PROJECT COST | 58,205 USD |
| SUPPORTED BY | THE WORLD BANK, KFW |
| FINANCED BY | IDCOL |
| EPC CONTRACTOR | Solargao Ltd |
| COMMISSIONING DATE | 08.08.2018 |
| TECHNICAL DETAILS | |
| FLOW RATE | 1695000 L/day |
| BORING DEPTH | 200 |

| Solar PV SIZE (kWp) | 30.78kwp |
|----------------------------|-----------------------|
| Individual Panel Size (Wp) | 270w |
| Number of Panels | 114 |
| Pump Size (kW) | 15kw |
| Controller Size (kW) | 15kw |
| GPS COORDINATES | 25.8888584,88.6415822 |

3. Detailed Commissioning Report



Figure 1: Master site for cluster-type grid integration at Chepuri Kandor




Figure 2: Slave Site design




Figure 3: Master Site design

3.1 System Summary of Grid Connection Infrastructure

| Size (kVA) 200 Step up or down | TRANSFORMER | |
|--|-------------|-----------------|
| Number of inverters | Size (kVA) | 200 |
| Size (kW) 25 | Туре | Step up or down |
| Number of Inverters | INVERTER | |
| Manufacturer Sunway Model STT-25KTL Serial Number 1102100102412076 (Site-1), 1102100102312076 (Site-2), 1102100102512076 (Site-3), 1102100102612076 (Site-4) SOLAR ARRAY (Site 1) TOTAL PV SIZE (kWp) SoW NUMBER OF ARRAY INDIVIDUAL PANEL SIZE (Wp) SOLAR ARRAY (Site 2) TOTAL PV SIZE (kWp) SOLAR ARRAY (Site 3) TOTAL PV SIZE (kWp) SOLAR ARRAY (SITE 3) TOTAL PV SIZE (kWp) SOLAR ARRAY (SITE 4) TOTAL PV SIZE (kWp) | | |

3.2 Array details

Site 1: Chepuri Kandor (GAZI 2)

| Number of Arrays/Strings | 6 | | |
|---------------------------------|----------------|-------------|-------------------|
| String 1 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 2 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 3 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 4 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 5 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| 0 | 7-1- | | |

| String Imp | 8.17 | 5.9 | During operation |
|---------------------------------|-------------------------|-------------|-------------------|
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 6 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM Material: Copper | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |

Site 2: Bocha Pukur (GAZI 2)

| Number of Arrays/Strings | 6 | | |
|---------------------------------|----------------|-------------|-------------------|
| String 1 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 2 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 3 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 4 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |

| String Voc | 36.3 | 33.63 | Using multi-meter |
|---------------------------------|-------------------------|-------------|-------------------|
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 5 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 6 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM Material: Copper | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |

Site 3: Kajol Porchim (GAZI 2)

| Number of Arrays/Strings | 6 | | |
|---------------------------------|-------------------------|-------------|-------------------|
| String 1 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM Material: Copper | | Material: Copper |
| Wire length to combiner box(m) | 700 | | |
| String 2 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM Material | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 3 | | | |
| Parameter | Designed Value | Field Value | Remark |

| No of panels in series | 20 | 20 | |
|---|---|--|--|
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 4 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 20 | 20 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 33.63 | Using multi-meter |
| String Vmp | 30.6 | 27.3 | During operation |
| String Imp | 8.17 | 5.9 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 5 | | | |
| | | | |
| Parameter | Designed Value | Field Value | Remark |
| Parameter No of panels in series | Designed Value 20 | Field Value 20 | Remark |
| | | | Remark |
| No of panels in series | 20 | 20 | Remark Using multi-meter |
| No of panels in series No of panels in parallel | 20 | 20 6 | |
| No of panels in series No of panels in parallel String Voc | 20 6 36.3 | 20 6 33.63 | Using multi-meter |
| No of panels in series No of panels in parallel String Voc String Vmp | 20 6 36.3 30.6 | 20 6 33.63 27.3 | Using multi-meter During operation |
| No of panels in series No of panels in parallel String Voc String Vmp String Imp | 20 6 36.3 30.6 8.17 | 20 6 33.63 27.3 | Using multi-meter During operation During operation |
| No of panels in series No of panels in parallel String Voc String Vmp String Imp Wire size (mm²) | 20 6 36.3 30.6 8.17 4.5 RM | 20 6 33.63 27.3 | Using multi-meter During operation During operation |
| No of panels in series No of panels in parallel String Voc String Vmp String Imp Wire size (mm²) Wire length to combiner box (m) | 20 6 36.3 30.6 8.17 4.5 RM | 20 6 33.63 27.3 | Using multi-meter During operation During operation |
| No of panels in series No of panels in parallel String Voc String Vmp String Imp Wire size (mm²) Wire length to combiner box (m) String 6 | 20 6 36.3 30.6 8.17 4.5 RM 700 | 20 6 33.63 27.3 5.9 | Using multi-meter During operation During operation Material: Copper |
| No of panels in series No of panels in parallel String Voc String Vmp String Imp Wire size (mm²) Wire length to combiner box (m) String 6 Parameter | 20 6 36.3 30.6 8.17 4.5 RM 700 | 20 6 33.63 27.3 5.9 | Using multi-meter During operation During operation Material: Copper |
| No of panels in series No of panels in parallel String Voc String Vmp String Imp Wire size (mm²) Wire length to combiner box (m) String 6 Parameter No of panels in series | 20 6 36.3 30.6 8.17 4.5 RM 700 Designed Value 20 | 20 6 33.63 27.3 5.9 Field Value 20 | Using multi-meter During operation During operation Material: Copper |
| No of panels in series No of panels in parallel String Voc String Vmp String Imp Wire size (mm²) Wire length to combiner box (m) String 6 Parameter No of panels in series No of panels in parallel | 20 6 36.3 30.6 8.17 4.5 RM 700 Designed Value 20 6 | 20 6 33.63 27.3 5.9 Field Value 20 6 | Using multi-meter During operation During operation Material: Copper |
| No of panels in series No of panels in parallel String Voc String Vmp String Imp Wire size (mm²) Wire length to combiner box (m) String 6 Parameter No of panels in series No of panels in parallel String Voc | 20 6 36.3 30.6 8.17 4.5 RM 700 Designed Value 20 6 36.3 | 20 6 33.63 27.3 5.9 Field Value 20 6 33.63 | Using multi-meter During operation During operation Material: Copper Remark Using multi-meter |
| No of panels in series No of panels in parallel String Voc String Vmp String Imp Wire size (mm²) Wire length to combiner box (m) String 6 Parameter No of panels in series No of panels in parallel String Voc String Vmp | 20 6 36.3 30.6 8.17 4.5 RM 700 Designed Value 20 6 36.3 30.6 | 20 6 33.63 27.3 5.9 Field Value 20 6 33.63 27.3 | Using multi-meter During operation During operation Material: Copper Remark Using multi-meter During operation |

Site 4: Kajol Kandor (GAZI 3)

| Number of Arrays/Strings | 6 | | |
|---------------------------------|-------------------------|-------------|-------------------|
| String 1 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 19 | 19 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 38.17 | 34.7 | Using multi-meter |
| String Vmp | 31.13 | 28.21 | During operation |
| String Imp | 8.67 | 6.71 | During operation |
| Wire size (mm²) | 4.5 RM Material: Copper | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |

| String 2 | | | |
|---------------------------------|----------------------------|-------------|-------------------|
| Parameter | Designed Value Field Value | | Remark |
| No of panels in series | 19 19 | | |
| No of panels in parallel | 6 | 6 6 | |
| String Voc | 36.3 | 34.7 | Using multi-meter |
| String Vmp | 30.6 | 28.21 | During operation |
| String Imp | 8.17 | 6.71 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 3 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 19 | 19 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 34.7 | Using multi-meter |
| String Vmp | 30.6 | 28.21 | During operation |
| String Imp | 8.17 | 6.71 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 4 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 19 | 19 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 34.7 | Using multi-meter |
| String Vmp | 30.6 | 28.21 | During operation |
| String Imp | 8.17 | 6.71 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 5 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 19 | 19 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 34.7 | Using multi-meter |
| String Vmp | 30.6 | 28.21 | During operation |
| String Imp | 8.17 | 6.71 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |
| String 6 | | | |
| Parameter | Designed Value | Field Value | Remark |
| No of panels in series | 19 | 19 | |
| No of panels in parallel | 6 | 6 | |
| String Voc | 36.3 | 34.7 | Using multi-meter |
| String Vmp | 30.6 | 28.21 | During operation |
| String Imp | 8.17 | 6.71 | During operation |
| Wire size (mm²) | 4.5 RM | | Material: Copper |
| Wire length to combiner box (m) | 700 | | |

3.3 On-grid Inverter details

| tem Remarks | | | | | |
|---------------------------|-----------------|-----------------|-----------------|----------|--|
| Inverter Manufacturer | Sunway | | | | |
| Number of Inverter | 4 | | | | |
| Model | S | STT-25KTL | | | |
| SN of Inverter 1 (Site 1) | 1 | 102100102412076 | | | |
| SN of Inverter 2 (Site 2) | 1 | 102100102312076 | (| | |
| SN of Inverter 3 (Site 3) | 1 | 102100102512076 | | | |
| SN of Inverter 4 (Site 4) | 1 | 102100102612076 | | | |
| Wire Size | 1 | 6RM | | | |
| Wire length | 1 | 230m | | | |
| Wire Material | (| Copper Wire | | | |
| COMMISSIONING DATA | | | | | |
| Inverter 1 | , | V _{oc} | V _{MP} | | |
| inverter i | Designed | Measured | Designed | Measured | |
| Input A | 612 | 546 | 726 | 672 | |
| Input B | 612 | 546 | 726 | 672 | |
| Inverter 2 | V _{oc} | | V _{MP} | | |
| | Designed | Measured | Designed | Measured | |
| Input A | 612 | 546 | 726 | 672 | |
| Input B | 612 | 546 | 726 | 672 | |
| Inverter 3 | V _{oc} | | V _{MP} | | |
| inverter 5 | Designed | Measured | Designed | Measured | |
| Input A | 612 | 546 | 726 | 672 | |
| Input B | 612 | 546 | 726 | 672 | |
| Inverter 4 | V _{oc} | | V _{MP} | | |
| mverter 4 | Designed | Measured | Designed | Measured | |
| Input A | 725 | 660 | 591 | 536 | |
| Input B | 725 660 591 536 | | | 536 | |

3.4 Protection Device details

| Arrestor | |
|------------------------------|---------------------|
| Item | Value |
| Lightning arrestor type | Horizontal Type |
| No. of LA: | 2 |
| LA height (>1.5meters) | 15ft |
| LA1 Earthing wire length (m) | 20ft |
| Wire size (mm ²) | Solid copper wire |
| LA2 Earthing wire length (m) | 20ft |
| Wire size (mm ²) | Solid copper wire |
| Earthing Rod | |
| Length (m) | 15ft |
| Туре | Solid Aluminum wire |

4. Implementation of the Grid Connection Pilot

The step-by-step process regarding the implementation of grid integration is given below -

Inception Meeting with Concerned Stakeholders: At the beginning of the project, an inception meeting was arranged with the concerned stakeholders, like IDCOL, BREB, SREDA, and local PBS to share the objectives, methodology, and work plan of the project.

Sharing Meeting with the Local Stakeholder: The second step was to share the objectives and ideas about project implementation and highlight the importance of their role in project implementation, with the local administration, agriculture office, *Polli Bidyut Somiti* (PBS) zonal and local office.

Focus Group Discussion: Conducting a focus group discussion of primary selected sites with farmers and local people. In this step, the operating hours and demand for irrigation from the farmers' side was also considered and noted.

Site Assessment and Selection: Conducting a site assessment or site selection is an important step for designing and installation of a system. During the site assessment, all necessary information to optimize system design was collected, to plan for a time-efficient and safe installation.

Design Finalization of the Innovation: The selected design of the project was finalized by sharing it with the concerned local stakeholders and IDCOL, SREDA, and PBS Authority. GAZI and the technical team of the innovation led the activities.

Procurement, Construction, Installation, and Monitoring: After getting funds from IDCOL, based on the modification, a new refined design of innovation was constructed. During construction, close monitoring was done so that the quality of the construction work was assured. Experts from GAZI and the local electricity authority used to visit the construction site and provide feedback and suggestions. Total procurement was conducted by the Organizational Procurement Committee (OPC) as per the procurement policies. The transmission line of 11 KV was constructed by the contractor of local PBS.

Commissioning of the Innovation: The process of testing the SIP grid integration system to confirm that it is producing electricity and interacting directly with the electricity grid is known as system commissioning. So, this commission activity is performed after the installation of the system within a certain time period.

Operation, Training, and Maintenance: After the construction of the SIP Grid Integration System, orientation training was arranged for the project staff and the caretaker of the pump for proper operation and maintenance of the system.

Monitoring & Data Collection: From the start of the operation of the pilot, various data collection and monitoring is being done to test its effectiveness. Both qualitative and quantitative data will be collected to measure the SIP Grid Integration System.

Final Report Preparation and Submission: A final report will be prepared and submitted based on all the work, data, activities, and conditions of the project, and information related to the innovation.

4.1 Technical details

| TRANSFORMER | |
|------------------------|---------------------------------|
| Size (kVA) | 200 |
| Туре | Step up or down |
| INVERTER | |
| Size (kW) | 25 |
| Number of Inverters | 4 |
| Manufacturer and Model | sunways and STT-25KTL |
| LT LINE | |
| Number of Poles | Cable Underground with PVC pipe |
| Length of Cable (m) | 10 m, 1231 m |
| Cable Size (mm) | 95 RM, 16 RM |
| Type of Cable | Insulated |
| HT LINE | |
| Number of Poles | 7 |
| Length of Cable (m) | 370 m |
| Type of Cable | Non insulated |

4.2 Financial details

| Total Cost of Grid Integration | 5,594,920/- |
|--------------------------------|-------------|
| Grant | 2,597,460/- |
| Sponsor Contribution | 2,997,460/- |
| IDCOL Loan | 0 |

Detailed cost with BoQ

| SN | ITEMS | Specification | Quantity | Unit (Nos./lot) | Cost (BDT) |
|----|---------------------|-------------------------|----------|-----------------|------------|
| 1 | Solar Grid Tie | Sunway | 4 | Pcs | |
| | Inverter | Max PV Input: 40000W | | | |
| | | IC: 30A | | | |
| | | OC: 25000 | | | |
| | | MPPT Effi: 99.9% | | | |
| 2 | MCCB & MCB | Circuit Breaker TP-63A | 04 | Pcs | |
| | | МСВ | | | |
| | | Circuit Breaker TP-63A | 04 | Pcs | |
| | | МССВ | | | |
| | | Circuit Breaker TP-200A | 01 | Pcs | |
| | | MCCB | | | |
| 3 | AC and DC Box | Walton PVC 12"x12" | 04 | Pcs | |
| | | Local MS (30"x24") with | | | |
| | | Bas Bar | 01 | Pcs | |
| 4 | Cable & Accessories | SQ Cables | 01 | Coil | |
| | | (1x4Rm NYYF for DC) | | | |
| | | 4x16Rm BYM-FR for AC | | | |

| | | | 14 | Coil | |
|------|--|--|----------------|-------|-------------|
| 5 | Transformer | Single-Phase Distribution Transformer Brand: TS Transformer Ltd. Capacity: 200 KVA | 01 | Pcs | |
| 6 | PBS Line construction with Fuse cut-out, lighting arrester and accessories | HT Three-phase line work with other equipment-related works up to meter. | 300 | Meter | |
| 7 | Cable tie, payroll & uPVC pipes | Local | As required | | |
| 8 | Underground cabling system | for 4 sites clustering | 4300 | Feet | |
| 9 | Meter | Hosab Meter | 4 | pcs | |
| 10 | Licensing | From the Electric Licencing Board | | | |
| 11 | Transportation, Labour, Testing, Commissioning | | | | |
| Tota | al Cost | | | | 5,594,920/- |

Note: They got bulk price for total work; therefore, there is no item wise price.

5. Monitoring and O&M

Ground water level, maximum power, energy generation, coverage, etc, are being monitored at the monthly frequency. Inspectors of IDCOL visit SIP sites on a routine basis, and if they find any technical problem, they inform the PO (Partner Organization) and the supplier. If the technical problem is identified by any supervisor of PO, they inform the supplier and IDCOL. In both cases, the monitoring team (HO) and the inspector dedicated to that site will track the issue until it is solved.

6. Conclusion

Potential Challenges:

- Local *Palli Bidyut Samitis* are not well acquainted with the Solar Irrigation Grid Integration Policy.
- There are several hidden and additional charges that hamper the total approval, installation, and operation of grid integrated systems.
- 100% solar power sharing in the grid from SIP is not possible due to following a policy of net metering system by the PBS.

The installation of the system and the continuous operation over the last few months show that the integration of the additional power to the grid is profitable. However, since the entire electricity generated is not integrated into the grid, the electricity tariff is low, and there is delay in getting revenue; more time is needed to determine its exact payback period for grid integration.

IWMI INDIA

IWMI India office, 2nd Floor, CG Block C, NASC Complex, DPS Marg, Pusa, Opp Todapur, New Delhi 110 012, India Email: iwmi-delhi@cgiar.org





The International Water Management Institute (IWMI) is an international, research-for-development organization that works with governments, civil society and the private sector to solve water problems in developing countries and scale up solutions. Through partnership, IWMI combines research on the sustainable use of water and land resources, knowledge services and products with capacity strengthening, dialogue and policy analysis to support implementation of water management solutions for agriculture, ecosystems, climate change and inclusive economic growth. Headquartered in Colombo, Sri Lanka, IWMI is a CGIAR Research Center with offices in 14 countries and a global network of scientists operating in more than 30 countries.

International Water Management Institute (IWMI)

Headquarters 127 Sunil Mawatha,Pelawatta, Battaramulla, Sri Lanka

Mailing address: P. O. Box 2075, Colombo, Sri Lanka Tel: +94 11 2880000 Fax: +94 11 2786854 Email: iwmi@cgiar.org www.iwmi.org